



A.M.E.C.
AL MANHAL ENGINEERING CONSULTANTS
المنهل للإستشارات الهندسية

PROJECT : Hattan Villa
PLOT NO. : Plot 3881109
CLIENT : M/S.Hattan Villa
CONTRACTOR : M/s BW Interiors

AL MANHAL ENG. CONSULTANTS
Tel: 04 - 2975000
Fax: 04 - 2975877
P.O.Box :14321
Dubai U.A.E

Material Submittal

Ref. No. BW-IM 456-MS-4-18
Revision No. 2

Date: 18-Aug-26

Originator of the Submittal: Vishnu Mohan

Position: Project Engineer

Types of Activites

- ☐ Architectural ☐ Structural ☐ Survey ☐ Electrical ☐ Mechanical ☒ HVAC
☐ Infrastructure ☐ Landscape ☐ Laboratory Report ☐ Safety ☐ Contractual Documents

Contractor to describe and specifying the documents submtted

Material Submittal - Valves & Accessories Rev.02 (Pegler)

Main Contractor's Signature:

Date: 18-Aug-26

Consultant's Received:

Date:

Consultant Resident Engineer's Comments:

- ☐ A - Approved ☒ B - Approved As Noted ☐ C - Not Approved, Resubmit ☐ D - Not Approved, Rejected

- The submitted valves and accessories are conditionally approved, subject to full compliance with the approved project specifications, drawings, and the comments below.
- All valves and accessories shall be from the approved manufacturers/vendors and shall comply with the approved Vendor List.
- The Contractor shall ensure that all valves are of the correct type, size, pressure rating, material, and end connection as specified and shown on the approved drawings.
- All valves shall be suitable for the intended service, operating pressure, temperature, and fluid and shall comply with the applicable project specifications and standards.
- The Contractor shall verify that the valve pressure rating and material of construction are suitable for the actual system operating conditions prior to installation.
- All valves and accessories shall be provided with the required certificates, test reports, compliance certificates, and manufacturer's technical data upon request.
- The Contractor shall ensure proper installation direction, accessibility, operation, and maintenance clearance for all valves and accessories in accordance with the approved shop drawings and manufacturer's recommendations.
- All valves shall be properly protected during transportation, storage, and installation. Any damaged or defective items shall be replaced.
- Any deviation from the approved specifications, manufacturer, type, or technical requirements shall be submitted as a formal deviation request for the Consultant's review and approval prior to procurement.
- Material approval is subject to inspection upon delivery and does not constitute approval of installation. Installation shall be inspected separately prior to testing and commissioning.
- The Contractor shall ensure that all valves and accessories are properly tested and commissioned as part of the relevant system before final acceptance.
- This approval is conditional upon full compliance with the above comments. Any deviation without prior written approval shall render this approval null and void.

Consultant's Signature:

A.Hussein

Date: 26-08-2026

Client's Signature:

Date:

Main Contractor Received:

Date:

Corrections or comments made relative to submittals during this review do not relieve the contractor from compliance with the contract requirement and specifications. This check is only for review of general conformance with the design concept of the project and general compliance with the information given in the contract documents.

IM_456_Hattan Villa**CRS-BW-IM 456-MS-4-18-Material Submittal Valves & Accessories Rev.02**

SL NO	Comments	Response
1	Full submittal should be provided for approval	Attached revised submittal
2	PRV valve should be part of the submittal	Material Submittal for the Pressure Reducing Valve (PRV) has been submitted separately under Ref. No. BW-IM 456-MS-4-20 – Material Submittal for Pressure Reducing Valve (PRV).
3	Provide Plumbing Valves manufactured by Pegler UK only.	Noted & Comply . Attached country origin certificate
4	Test certificate to be provided	Attached
5	Complete valve package sample to be provided	Noted
6	All valves of the same type shall be of the same manufacturer with at least PN20.	Ball Valve - Proposed PN25 Float Valve -Proposed PN16 ,Kindly note that the DEWA main water pressure is only 3 bar and the working pressure upto 16 Bar .
7	PN rating shall be as per project specification and site requirement.	Noted & Comply
8	Clarify: selecting valves with different pressure rating which are used in the same system pressure.	Please note that, as per the Pegler product specifications, the pressure rating for ball valves from ½" to 2" sizes is PN25. As per our design requirements, all ball valves are below 2" size.
9	All valves should be WRAS certified.	Comply . Attached certificate for your reference

10	Provide third-party certification for the pressure rating of the valves and strainers.	Attached
11	Original test certificate shall be provided.	Attached
12	The warranty certificate should be submitted without any conditions, signed and stamped by the supplier and main contractor	Attached draft warranty letter for your reference . The warranty period will be 5 years from the date of TOC, covering any manufacturing defects.

JUNAID SAN & ELE MAT TRDG LLC

Dealers in Plumbing & Sanitary ware Products

P.O. Box 34862, Dubai, U.A.E.

Tel: 04-2367723 Fax: 04-2367250

E-mail: project@junaid.ae

Web: www.junaidworld.com

MATERIAL SUBMITTAL

- Project Name : IM_456_Hattan Villa
- Landlord : Hattan Villa
- Client : Hattan Villa
- Plot No. : 3881109
- Location : Al Thanyah Third
- MEP Consultant : Al Manhal Engineering Consultants
- Main Contractor : BW Interiors
- MEP Contractor : BW Interiors MEP
- Product : Pegler – UK – Plumbing valves

JUNAID SANT. & ELECT. MAT. TR. LLC

P.O. Box 34862, Dubai, U.A.E.
Tel: +971 4 236 7723, Fax: +971 4 236 7750
E-mail: project@junaid.ae

INDEX

- 1. Company Profile**
- 2. Company trade licence and related certificates**
- 3. Material schedule**
- 4. County of Origin**
- 5. Compliance statement**
- 6. Catalogue**
- 7. Certificates**
- 8. Draft Warranty**
- 9. Approvals**

JUNAID SANT. & ELECT. MAT. TR. LLC

P.O. Box 34862, Dubai, U.A.E.

Tel: +971 4 236 7723, Fax: +971 4 236 7750

E-mail: project@junaid.ae



1. Company Profile



PLUMBING MATERIALS PROFILE

www.junaidworld.com



ABOUT US





JSEMT has the broadest and most diverse range of products available in the UAE, and we provide our customers with only the highest quality goods and services at the most competitive prices. We have built strong, long-lasting partnerships with many of the world's leading brand names, and are the trusted suppliers of products from manufacturing companies.

**We promise excellent
& speedy service,
every single time.**



Since 1994

Our Branches



key Highlights



TOTAL ITEMS WE DEAL=25,000+

We believe in

Growing Together

Carrying a Legacy of 25+ years, JSEMT provides a reliable and healthy business channel partnership for the supply of Plumbing Materials. offering the widest range of products and services at competitive prices, we are the preferred choice for our customers.

Our story

With the vision to 'Grow Together'. Junaid Sanitary and Electrical Material Trading LLC (JSEMT) Was founded in 1994. JSEMT is the premier supplier of the highest quality plumbing and sanitary Ware equipment's in United Arab Emirates.

JSEMT's team have expertise in electromechanical products and professional management, which makes them efficient in delivering high customer value. JSEMT continues to grow and our expert team is ideally placed to serve UAE's rapidly growing construction sector.

JSEMT has built a strong, long-lasting partnership with the world's leading brands and are the trusted suppliers of products from manufacturing companies including ARISTON, ZENITH, PEGLER, ESPA, RAKtherm, THAI MALLEABLE, COSMOPLAST, HEPWORTH, MULTIKWIK, VERA, VIEGA, WEDNUSBURY, ATLANTIC, KAJ, ITPLAST, PARABOND, JOFLEX, FLOWFLEX, MPI, BMETERS, ESVIT .

As a company, JSEMT sets the gold standard for the plumbing services industry. with our unparalleled reputation for excellent customer service, our experience and strong vision for the future, we are uniquely poised for greater success and further business development in the region.

JUNAID SANT. & ELECT. MAT. TR. LLC

P.O. Box 34862, Dubai, U.A.E.

Tel: +971 4 236 7723, Fax: +971 4 236 7750

E-mail: project@junaid.ae

2. Company trade licence and related certificates



رخصة تجارية Commercial License

تفاصيل الرخصة / License Details

License No.	509853	رقم الرخصة
Business Name	JUNAID SANITARY & ELECTRICAL MATERIALS TRADING (L.L.C.) (DUBAI BR)	الاسم التجاري
License Category	Dep. of Economic Development	فئة الرخصة
Legal Type	Branch of Company Registered in other emirates	الشكل القانوني
Expiry Date	10/01/2027	تاريخ الإصدار
D&B D-U-N-S ® N 561637088	رقم العالمى	رقم الرخصة الام
Register No.	رقم السجل التجارى	عضوية الغرفة

الاطراف / License Members

Share / الحصص	Role / الصفة	Nationality / الجنسية	Name / الإسم	No./ رقم الشخص
Co. Owner / مالك الشركة	United Arab Emirates / الامارات	جنيد لتجارة لوازم التمديدات الصحية والكهربائية (ش. ذ.م.م)	JUNAID SANITARY AND ELECTRICAL REQUISITES TRADING L.L.C	443667
Manager / مدير	India / الهند	انوف احمد ك شيخ شابو	ANUFF AHAMMED K SHICK SHABU SAHEB	112717
Manager / مدير	India / الهند	نشير احمد احمد ك شيخ شابو صاحب	NASHEER AHAMMAD K SHEIK SHABU SAHEB	175167

أنشطة الرخصة / License Activities

Activity	Status	النشاط
Electrical Fittings Trading	Active	تجارة ادوات التمديدات الكهربائية
Sanitary Ware Trading	Active	تجارة الادوات الصحية

Print Date 15/01/2026 12:52 تاريخ الطباعة

Receipt No.

رقم الإيصال



يمكنك الآن تجديد رخصتك التجارية من خلال الرسائل النصية القصيرة، أرسل رقم الرخصة إلى 6969 (دو/ اتصالات) للحصول على اذن الدفع.

Now you can renew your trade license by sending a text message (SMS). Send your trade license

number to 6969 (Du/ Eticalat) to receive payment voucher

وثيقة إلكترونية معتمدة وصادرة بدون توقيع من دائرة الاقتصاد والسياحة في دبي. لمراجعة صحة البيانات الواردة في الرخصة يرجى مسح رمز الاستجابة السريعة

This is a certified e-document issued without signature by the department of Economy and Tourism. Kindly scan the QR Code to verify the certificate

Get FREE access to Zoho One for the first year
احصل على زوهو ون مجاناً للسنة الاولى



Zoho.com/det



العنوان / Address			
Phone No	971-4-2353455	تليفون	P.O. Box 34862 صندوق بريد
Fax No	971-4-3330694	فاكس	Parcel ID 114-295 رقم القطعة
Mobile No	971-55-8946801	هاتف متحرك	Email junaidadmin@junaid.ae البريد الإلكتروني
مكتب رقم 102 ملك منذر عبدالله عيسى ال ثاني - ديرة - البطين			
الملاحظات / Remarks			
تم نقل الموقع 13/9/2017			

Print Date 15/01/2026 12:52 تاريخ الطباعة

Receipt No.

رقم الإيصال



يمكنك الآن تجديد رخصتك التجارية من خلال الرسائل النصية القصيرة، أرسل رقم الرخصة إلى 6969 (دو/ اتصالات) للحصول على اذن الدفع.

Now you can renew your trade license by sending a text message (SMS). Send your trade license

number to 6969 (Du/ Eticalat) to receive payment voucher.

Get FREE access to Zoho One for the first year

احصل على زوهو ون مجاناً للسنة الاولى



Zoho.com/det

وثيقة إلكترونية معتمدة وصادرة بدون توقيع من دائرة الاقتصاد والسياحة في دبي. لمراجعة صحة البيانات الواردة في الرخصة يرجى مسح رمز الاستجابة السريعة
This is a certified e-document issued without signature by the department of Economy and Tourism. Kindly scan the QR Code to verify the certificate



بيانات التصريح / Permit Details				
Permit Nr	186697			رقم التصريح
Permit Type	مستودع			نوع التصريح
Warehouse				
Expiry Date	10/01/2027	تاريخ الإنتهاء	Issue Date	05/01/2014
Description	مستودع رقم : s1 للتخزين فقط - المالك : مؤسسة دبي العقارية - المنطقة : راس الخور الصناعية - رقم قطعة الارض : 613-1360 - قيمة عقد الايجار: 100 الف درهم			
Remarks	مستودع للتخزين فقط - عدم مزاولة العمل في المستودع			

بيانات التصريح / Permit Details				
Permit Nr	9938671			رقم التصريح
Permit Type	إعلانات الاسماء التجارية			نوع التصريح
Business name Sign Boards				
Expiry Date	10/01/2027	تاريخ الإنتهاء	Issue Date	10/01/2009
Description	JUNAID - فرع دبي - (ش. ذ. م. م) - فرع دبي - JUNAID (SANITARY & ELECTRICAL MATERIALS TRADING (L.L.C.) (DUBAI BR			تاريخ الإصدار
Remarks	تثبيت لافتته بلاستيك على السور الخاص بالموقع			شرح
ملاحظات				

بيانات التصريح / Permit Details				
Permit Nr	39265			رقم التصريح
Permit Type	إعلانات الاسماء التجارية			نوع التصريح
Business name Sign Boards				
Expiry Date	10/01/2027	تاريخ الإنتهاء	Issue Date	27/08/2008
Description	جنييد لتجارة لوازم التمديدات الصحية والكهربائية (ش. ذ. م. م) - فرع دبي			شرح
JUNAID SANITARY & ELECTRICAL MATERIALS TRADING (L.L.C.) (DUBAI BR)				
Remarks	تثبيت اللافتة على واجهة المحل حسب القياسات اللافتات المجاورة			ملاحظات

Print Date 15/01/2026 12:52 تاريخ الطباعة

Receipt No.

رقم الإيصال



يمكنك الآن تجديد رخصتك التجارية من خلال الرسائل النصية القصيرة، أرسل رقم الرخصة إلى 6969 (دو/ اتصالات) للحصول على اذن الدفع.

Now you can renew your trade license by sending a text message (SMS). Send your trade license

number to 6969 (Du/ Eticalat) to receive payment voucher

Get FREE access to Zoho One for the first year

احصل على زوهو ون مجاناً للسنة الاولى



Zoho.com/det

وثيقة إلكترونية معتمدة وصادرة بدون توقيع من دائرة الاقتصاد والسياحة في دبي. لمراجعة صحة البيانات الواردة في الرخصة يرجى مسح رمز الاستجابة السريعة
This is a certified e-document issued without signature by the department of Economy and Tourism .Kindly scan the QR Code to verify the certificate

شهادة تسجيل العضوية Membership Certificate

License no.	509853
Membership no.	52933
Registration no.	1021282
Business Name	JUNAID SANITARY AND ELECTRICAL MATERIALS TRADING (L.L.C.) (DUBAI BR)
Legal Status	Branch of Company Registered in
Activity	Sanitary Ware Trading Electrical Fittings Trading
Member Since	10/01/1999
Date of Issue	10/01/1999
Expiry Date	10/01/2027

رقم الرخصة	509853
رقم العضوية	52933
رقم السجل التجاري	1021282
الاسم التجاري	جنيد لتجارة لوازم التمديدات الصحية والكهربائية (ش. ذ. م.) - فرع دبي
الشكل القانوني	فرع لشركة مقرها في امانة أخرى
نوع النشاط	تجارة الادوات الصحية تجارة ادوات التمديدات الكهربائية
تاريخ الإنتساب	10/01/1999
تاريخ الإصدار	10/01/1999
تاريخ الإنتهاء	10/01/2027

Remarks

This certificate shall be invalid incase of any alteration without chamber's authorization

For online verification of this Certificate, please visit our website
<http://www.dubaichamber.ae/verify>

غرفة تجارة وصناعة دبي
Dubai Chamber of Commerce & Industry

P.O. Box 1457 - Dubai, U.A.E. | Tel (Within UAE) 800 CHAMBER (800 2426237) | Tel (Outside UAE) (+971) 4 2280000 هـاتف
فاكس (+971) 4 2211646 | customercare@dubaichamber.ae | www.dubaichamber.ae

الملاحظات

تعتبر هذه الشهادة لاغية في حال أي كسب أو تعديل عليها دون اعتماد ذلك من الغرفة

للتأكد من صحة بيانات الشهادة يرجى الرجوع إلى موقع الغرفة
<http://www.dubaichamber.ae/verify>



FIRST QUALITY CERTIFICATION

Certificate of Registration

This certificate is hereby granted to the organization

JUNAID SANITARY & ELECTRICAL MATERIALS TRADING (L.L.C) (DUBAI BR)

P.O BOX NO: 34862, OFFICE NO: 597-266, JUNAID GROUP BUILDING, DUBAI INVESTMENTS PARK 2, DUBAI, UAE

This has been certified that the management system of the above organization has been audited and found to be in compliance with the First Quality Certification requirements for registration of the management system standard detailed below:

ISO 9001:2015

(Quality Management System)

Scope of work

- Sanitary Ware Trading
- Electrical Fittings Trading
- Importers, Exporters and Distributors of Plumbing, Sanitary and Electrical Materials

Certification Registration No: FQC/Q/1530/AE

Initial Issue Date : 14 December 2022

1st Surveillance : 07 December 2026

Re-issue Date : 08 December 2025

2nd Surveillance : 07 December 2027

Certificate Expiry : 07 December 2028

(Subject to the company maintaining its system to the required Standard)




Chief Executive Officer

This Certificate is subject to satisfactory annual assessment.

Accredited by Accreditation Service for Certifying Bodies LLC, 8 The Green, Dover, DE, 19901, United States www.ascb.com

Building C112, Mezzanine Floor, M03, Mohammed Bada Zayed City, ME9, Mussafah, P.O. Box 92715 Abu Dhabi, United Arab Emirates

The authenticity of this certificate can be verified online www.firstqualitycertification.ae or by email to the Head Office Info@firstqualitycertification.ae

JUNAID SANT. & ELECT. MAT. TR. LLC

P.O. Box 34862, Dubai, U.A.E.
Tel: +971 4 236 7723, Fax: +971 4 236 7750
E-mail: project@junaid.ae



JUNAID SANT. & ELE. MAT. TRDG. LLC

P.O. Box 34862, Dubai, U.A.E.

Tel: +971 4 236 7723, Fax: +971 4 236 7250

E-mail: project@junaid.ae

LIST OF PROPOSED MATERIALS

Project Name : IM_456_Hattan Villa
Landlord : Hattan Villa
Client : Hattan Villa
Plot No. : 3881109
Location : Al Thanyah Third
MEP Consultant : Al Manhal Engineering Consultants
Main Contractor : BW Interiors
MEP Contractor : BW Interiors MEP
Product : Pelger – Valves - UK

SR.NO	ITEM DESCRIPTION	MATERIAL	SIZES	PRESSURE RATING	MODEL	BRAND & ORIGIN
1	Ball Valve	BRASS	½" to 2"	PN 25	PB100	PEGLER - UK
2	Float valve	BRASS	½" to 2"	PN 16	855	PEGLER - UK



JUNAID SANT. & ELECT. MAT. TR. LLC

P.O. Box 34862, Dubai, U.A.E.
Tel: +971 4 236 7723, Fax: +971 4 236 7750
E-mail: project@junaid.ae



JUNAID SANT. & ELECT. MAT. TR. LLC

P.O. Box 34862, Dubai, U.A.E.
Tel: +971 4 236 7723, Fax: +971 4 236 7750
E-mail: project@junaid.ae

5. Compliance statement



**(G+F+ROOF) RESIDENTIAL VILLA
ON PLOT NO (3881109)–AI THANYAH THIRD Dubai – UAE.**

1.6 Reference Standards

BS 759 - Part1:	Valves, mountings and fittings
BS 1010	Draw off tap and stop valves for water services (screw down pattern)
BS 1010 - Part2:	Draw off taps and aboveground stop valves.
BS 1212:	Float operated valves (excluding floats).
BS 1212 - Part1:	Piston type
BS 1212 - Part2:	Diaphragm type (brass body)
BS 1212 - Part3:	Diaphragm type (plastics body)
BS 1503:	Steel forgings for pressure purposes.
BS 1968:	Floats for ball valves (copper).
BS 2456:	Floats (plastic) for ball valves for hot and cold water.
BS 2767:	Manually operated copper alloy valves for radiators.
BS 2879:	Draining taps (screwdown pattern).
BS 5150:	Cast iron wedge and double disc gate valve for general purpose.
BS 5151:	Cast iron gate (parallel slide) valves for general purposes.
BS 5152:	Cast iron globe and globe stop and check valves for general purposes.
BS 5153:	Cast iron check valves for general purposes.
BS 5154:	Copper alloy globe, globe stop and check, check and gate valves.
BS 5156:	Diaphragm valves.
BS 5157:	Steel gate (parallel slide) valves for general purposes.
BS 5158:	Cast iron plug valves.
BS 5159:	Cast iron and carbon steel ball valves for general purposes.
BS 5160:	Steel globe valves, globe stop and check valves and lift type check valves.
BS 5163:	Predominantly key-operated cast iron gate valves for water works purposes.
BS 5235:	Dial-type expansion thermometers.
BS 5353:	Steel plug valves.
BS 5433:	Underground stop valves for water services.
BS 6683:	Guide to installation and use of valves.
BS 6755:	Testing of valves.
BS 6759:	Safety valves.
BS 7350:	Double regulating globe valves and flow measurement devices for heating and chilled water systems.
BS 7478:	Guide to selection and use of thermostatic radiator valves.
BS EN 593:	Industrial valves-metallic butterfly valves.
BS EN 837:	Pressure gauges.
BS EN 837-1:	Bourdon tube pressure gauges - dimensions, metrology, requirements and testing.
BS EN 1982:	Copper and copper alloy-ingots and castings.
BS EN 10213:	Technical delivery conditions for steel castings for pressure purposes.

2.0 PRODUCTS

2.1 Materials

Generally, all valves of the same type shall be of the same manufacturer. All gate, globe, angle, and swing check valves as a group shall be of the same manufacturer.

All valves 50 mm and smaller shall be threaded and have brass bodies.

All valves 65 mm and larger shall be Iron Body brass Mounted (IBBM) type, i.e. with brass trim, and shall be flanged (or grooved for grooved coupling joints).

All valves 100 mm and larger mounted in excess of 2.15 m above the floor in mechanical rooms shall be equipped with chain operators. Extend chains to within 2 m of floor.

All isolation valves shall be ball valves and gate valves shall not be accepted.

**(G+F+ROOF) RESIDENTIAL VILLA
ON PLOT NO (3881109)–AI THANYAH THIRD Dubai – UAE.**

Each valve shall be marked (engraved, stamped, or cast on each valve or metal tag, permanently attached to the valve) at the factory with the following minimum information:

- a) Manufacturer's Name.
- b) Catalogue or Figure No.
- c) Size and Pressure Class.

Arrows to indicate direction of flow on check, globe, angle, non-return, and eccentric plug valves.

2.2 Gate Valves

2.2.1 General:

Furnish valves 300 mm and smaller designed for minimum PN16 non shock water, oil and gas working pressure. Valves 350 mm through 610 mm, shall be designed for minimum PN16.

2.2.2 Size 50 mm and Smaller.

Furnish brass valves with screwed-in bonnet, non-rising stem, solid wedge disc, and threaded ends. Pressure rating PN16.

2.2.3 Size 65 mm and Larger.

Furnish Iron Body brass Mounted (IBBM) valves, i.e. cast iron body bronze trim valves, with bolted bonnet, non-rising stem, solid wedge disc, flanged ends, and renewable seat rings.

2.3 Globe Valves

2.3.1 Size 50mm and Smaller.

Furnish valves designed for minimum PN16 nonshock water, oil, and gas working pressures. Valves shall have union bonnets, integral seats, and renewable teflon discs. Valves shall permit disc and bonnet replacement without removing valves from piping.

2.3.2 Size 65 mm and Larger.

Furnish valves designed for minimum PN16 water, oil, and gas working pressure. Valves shall have bolted bonnets, guided brass or bronze faced disc, outside screw and yoke, (O S and Y) and flanged ends. Discs and seats shall be renewable without removing valves from line.

2.4 Double Regulating Valves

2.4.1 Size 50mm and smaller.

Furnish brass double regulating valve designed for minimum PN16. Parabolic and slotted disk double regulating device. Screwed bonnet, rising stem, hand wheel operated with micrometer style indicator.

2.4.2 Size 65mm and larger.

Furnish cast iron double regulating valve for minimum PN16. Fitted with EPDM coated regulating disk, double regulating device and indicator, flanged to BS 4504 PN16. Inside screw, non-rising copper alloy stem, back seating feature.

2.4.3 Balancing valves shall comprise a metering station and a close coupled double regulating valve. The metering station, containing an orifice shall be fitted with test points so that the pressure drop across

**(G+F+ROOF) RESIDENTIAL VILLA
ON PLOT NO (3881109)–AI THANYAH THIRD Dubai – UAE.**

the orifice can be measured. The commissioning set shall provide $\pm 5\%$ accuracy and should be installed with a minimum of 5 times pipe diameter uninterrupted upstream length of straight pipe.

2.5 Check Valves

2.5.1 Water, Oil, and Steam, size 50 mm and smaller.

Furnish swing valves designed for minimum PN16 nonshock water, oil, and gas working pressures. Valves shall have renewable discs and side plugs and regrindable, integral seats. Discs shall be renewable and seats regrindable without removing valves from the line.

2.5.2 Size 65 mm and Larger Water Check Valves.

Valves shall be silent type spring loaded of the double door or wafer style. Valves shall be designed for minimum PN16 non shock water working pressure.

Double door valves shall have bronze body, aluminum bronze or stainless steel disc, stainless steel spring and hinge pin, and Butyl rubber sheet. Wafer style valves shall have cast iron or semi-steel body, bronze disc, stainless steel spring, and Butyl rubber sheet.

2.6 Butterfly Valves

2.6.1 Furnish valves designed for minimum PN16 and 120 degrees C. water service. Valves shall have extended necks. Operator shall be 10-position lever lock for sizes 50 - 100 mm and totally enclosed and sealed worm gear actuators with 4-arm or wheel handle for sizes 150 mm and larger. Infinite adjustment and memory stop options shall be included. Valves shall be bi-directional suitable for drop-tight shut-off at full rated pressure with flow in either direction.

2.6.2 Materials.

Body: Cast or ductile iron.

Disc: Bronze, aluminum bronze or stainless steel.

Stem - Type 416 stainless steel.

Seat - Ethylene Propylene Diene Terpolymer (EPDM).

2.7 Pressure Reducing Valves.

2.7.1 Domestic Water Lines.

Pressure reducing valves shall be pilot controlled, hydraulically operated, diaphragm type with a low by-pass capability. The low-flow by-pass capability shall be achieved by using a balanced direct acting PRV as an integral part of the main valve. At very low flows when the main valve is almost completely closed, to prevent the possibility of cavitation the direct acting valve shall by-pass the main valve and maintain flow.

PRVs shall be brass construction including the trim. The pressure reducing valves shall be suitable for maximum working pressure that exist within the system and downstream pressure should be site adjustable between 2 and 4 bar. Refer to Schematic drawings for the minimum locations at which PRV's shall be required.

2.7.2 Fire protection services:

**(G+F+ROOF) RESIDENTIAL VILLA
ON PLOT NO (3881109)–AI THANYAH THIRD Dubai – UAE.**

Where required for installation in the Fire Protection Systems, the PRV shall be direct acting, site adjustable type, of brass (upto 50mm) or bronze (65mm and larger) construction. The PRV shall be UL listed and FM approved.

2.8 Relief Valves.

2.8.1 Domestic Water Temperature and Pressure Relief Valve.

On hot water storage tanks provide an ASME rated thermostatic, self-closing, temperature and pressure relief valve, located in the relief valve openings of tanks. Valve shall have a minimum thermal discharge capacity equal to the input capacity of the heater standard pressure setting of 600 kPa and standard temperature setting of 100 degrees C. Relief valve pipe to discharge to floor drain.

2.9 Ball Valves.

2.9.1 General:

Valves shall be non-blowout stem design. Quarter turn of handle shall fully open or close valve. Handle position shall indicate whether valve is open or closed. Handle stops shall be a permanent, integral part of the body.

2.9.2 Size 50 mm and Smaller.

Valves shall be standard port, 2-piece construction with screwed ends. Valves shall be designed for minimum PN16.

Valves shall have brass body, stainless steel ball, bronze handle with vinyl grip, and replaceable teflon seats.

2.9.3 Size 65 mm and Larger.

Valves shall be standard port, BS 5159 with flanged ends. Valves shall be designed for minimum PN16 working pressure.

Valves shall have bronze body, stainless steel ball, replaceable teflon seats, and steel stem and handle.

Where required for installation in the fire protection system, the ball valves shall be UL/FM approved.

2.10 Float Valves

2.10.1 Float valves shall be installed as indicated in the drawings to provide consistent level control in reserve supply water storage tanks. The valve shall meet the requirements of the Water Byelaws for air gaps and shall be constructed throughout in approved materials and shall prevent back siphoning. Inlet flow shall be co-axial with the piston movement, to ensure high discharge capacity and smooth, quiet operation. The valve shall have 'O' ring piston seals, resilient seated disk, Dezincification resistant bronze fabricated approved solder and shall be hydraulically tested to ensure buoyancy and constructed in accordance with BS1968.

2.10.2 Brass equilibrium float valves 80 and above shall be flanged end, flat faced and drilled to suit BS4504 PN16.

2.10.3 Brass equilibrium float valves upto 50 shall be screwed end BS2779 parallel and shall be provided complete with back nut.

**(G+F+ROOF) RESIDENTIAL VILLA
ON PLOT NO (3881109)–AI THANYAH THIRD Dubai – UAE.**

2.10.4 Floats for valve sizes 80mm and above shall be of copper.

2.11 Solenoid Valves

2.11.1 Electrically operated solenoid valves shall be single phase 220V and shall be rated for the system pressure.
The Solenoid Valves shall be UL/FM approved.

2.12 Bib Taps

2.12.1 Bib-cocks shall be in accordance with BS 1010 : 1973. They shall be provided with hose union nosepiece and hand wheel operated.

2.13 Automatic Air Valves

2.13.1 Automatic air valves shall have a brass body with bolted cover and a 9mm top outlet.
2.13.2 They shall each incorporate a suitable float mounted on a stainless steel spindle terminating in a needle valve for closure against a stainless steel seating at the outlet. For low pressure systems the valve shall be provided with a test cock and a brazed float, but for medium and high pressure systems the float shall be of stainless steel.
2.13.3 Automatic air valves for low pressure systems shall, incorporate an internal ball check valve at inlet to prevent air entry to the system. Automatic air valves for cold water services shall be to the approval of the local water authority.

2.14 Strainers

Up to and including DN50 strainers shall be manufactured from bronze and shall be of the 'Y' type with bolted cap, PN16 temperature/pressure rating. Strainers above DN50 shall be manufactured from cast iron and shall be of the 'Y' type with bolted cap, PN16 temperature/pressure rating and shall be complete with drilled and tapped caps complete with drain cocks. Strainers shall be provided with a medium grade screen from stainless steel sized such that in their clean condition the maximum pressure drop at the design flow rate shall not exceed 6kPa. For chilled water the mesh shall be stainless steel and for water services the mesh shall be of copper.

2.15 MAXIMUM FLOW RATE REQUIRED FOR FIXTURE FITTINGS
(Contractor shall propose fixtures with less flow rate than the following to comply with green building Requirements)

FIXTURE OF FIXTURE FITTING	PERCENTAGE REDUCTION
Bathroom Taps, Private	6 Liters/min at 417.7 kPa
Bathroom Taps, Public	1.9 Liters/min at 417.7 kPa
Shower Head	9.5 Liters/min at 551.6 kPa
Kitchen Sink Faucet	6 Liters/min at 417.7 kPa
Bidets	6 Liters/min

**(G+F+ROOF) RESIDENTIAL VILLA
ON PLOT NO (3881109)–AI THANYAH THIRD Dubai – UAE.**

Toilets (Dual Flush)	6/4 Liters/flushing cycle (full/low)
----------------------	--------------------------------------

3.0 EXECUTION

3.1 *Preparation*

Provide valves at each piece of equipment to isolate equipment from its connected system. Locate strainers and valves as necessary to provide easy isolation and cleaning of strainers.

Strainers shall be installed ahead of all automatic valves and elsewhere as indicated on Drawings. Provide a ball valve and 1.5 m of rubber hose in the blow off opening of each strainer.

Unions shall be provided adjacent to each screwed type valve and shall be on the outlet side of the valve.

3.2 *Installation/Application/Performance/Erection*

3.2.1 Properly align piping before installation of valves in an upright position; operators installed below the valves will not be accepted.

3.2.2 Install valves in strict accordance with valve manufacturer's installation recommendations. Do not support weight of piping system on valve ends.

3.2.3 Install all valves with the stem in the upright position. Valves may be installed with the stem in the horizontal position only where space limitations do not allow installation in an upright position or where large valves are provided with chain wheel operators. Where valves 50-65mm and larger are located more than 4m above mechanical room floors, install valve with stem in the horizontal position and provide a chain wheel operator. Valves installed with the stems down, will not be accepted.

3.2.4 Prior to flushing of piping systems, place all valves in the full-open position.

3.2.5 Flanged valves shall be installed between flanges.

3.2.6 Shut-Off Valves

Install shut-off valves at all equipment, at each branch take-off from mains, and at each automatic valve for isolation or repair.

3.2.7 Balancing Valves

Provide balancing valves for all major equipment and at each major branch takeoff and at the discharge of each pump as indicated on drawings and details.

3.2.8 Calibrated balance valves:

Install where indicated on the drawings and details for balancing of hydronic systems.

3.2.9 Drain Valves

Provide drain valves for complete drainage of all systems. Locations of drain valves include low points of piping systems, equipment locations specified or other locations required for drainage of systems.

JUNAID SAN & ELE MAT TRDG. LLC

P.O. Box 34862, Dubai, U.A.E.

Tel : 00971-4-2367723 Fax : 00971-4-2367250

E-mail : junaidse@emirates.net.ae

Compliance Statement

Project Name : IM_456_Hattan Villa
Landlord : Hattan Villa
Client : Hattan Villa
Plot No. : 3881109
Location : Al Thanyah Third
MEP Consultant : Al Manhal Engineering Consultants
Main Contractor : BW Interiors
MEP Contractor : BW Interiors MEP
Product : Pelger – Valves - UK

SL NO.	SPECIFICATION	COMPLY	REMARKS
2.7			
2.9	Ball Valves. 2.9.1 General : Valves shall be non-blowout stem design. Quarter turn of handle shall fully open or close valve. Handle position shall indicate whether valve is open or closed. Handle stops shall be a permanent, integral part of the body. 2.9.2 Size 50 mm and Smaller : Valves shall be standard port, 2-piece construction with screwed ends. Valves shall be designed for minimum PN16. Valves shall have brass	Comply as Noted	We proposed PB100 brass ball valve, PN25 pressure rating for ½" to 2", Full bore, quarter turn operation, red lever handle. • Body – Brass • End piece – Brass • Ball, chrome plated – Brass



JUNAID SAN & ELE MAT TRDG. LLC

P.O. Box 34862, Dubai, U.A.E.

Tel : 00971-4-2367723 Fax : 00971-4-2367250

E-mail : junaidse@emirates.net.ae

	body, stainless steel ball, bronze handle with vinyl grip, and replaceable Teflon seats. 2.9.3 Size 65 mm and Larger : Valves shall be standard port, BS 5159 with flanged ends. Valves shall be designed for minimum PN16 working pressure. Valves shall have bronze body, stainless steel ball, replaceable teflon seats, and steel stem and handle. Where required for installation in the fire protection system, the ball valves shall be UL/FM approved.		• Stem – Brass • Seats – PTFE • Gland – PTFE • Gland nut – Brass • Handle nut – Steel
2.10	Float Valves 2.10.1 Float valves shall be installed as indicated in the drawings to provide consistent level control in reserve supply water storage tanks. The valve shall meet the requirements of the Water Byelaws for air gaps and shall be constructed throughout in approved materials and shall prevent back siphoning. Inlet flow shall be co-axial with the piston movement, to ensure high discharge capacity and smooth, quiet operation. The valve shall have 'O' ring piston seals, resilient seated disk, Dezincification resistant bronze fabricated approved solder and shall be hydraulically tested to ensure buoyancy and constructed in accordance with BS1968. 2.10.2 Brass equilibrium float valves 80 and above shall be flanged end, flat faced and drilled to suit BS4504 PN16. 2.10.3 Brass equilibrium float valves upto 50 shall be screwed end BS2779 parallel and shall be provided complete with back nut. 2.10.4 Floats for valve sizes 80mm and above shall be of copper.	Comply	We proposed 855 M0H Float Valve Portsmouth pattern high pressure. Maximum cold working pressure 16 bar at temperature up to 85 deg. C. manufactured in accordance with ISO 9001:2008 Quality Management System. Proposed 855 Float Valve with male threaded ends & PVC float.
End of List			




JUNAID SANT. & ELECT. MAT. TR. LLC

P.O. Box 34862, Dubai, U.A.E.
Tel: +971 4 236 7723, Fax: +971 4 236 7750
E-mail: project@junaid.ae




855 MOH Float valve



specification

- Portsmouth pattern
- * high pressure
- brass body




Dimensions (mm)


	D	DN1/DN2	Dr1	Dr2	Dr3	L1	L2	L3	slw1	X1	X2	Y1	Y2
DN15	23.0	½"	23.0	21.0	7.0	48.0	64.0	259.0	13.0	284.0	285.0	138.0	165.0
DN20	30.0	¾"	35.0	26.0	7.0	58.0	77.0	295.0	13.0	326.0	304.0	157.0	260.0
DN25	27.0	1"	43.0	33.0	10.0	66.0	90.0	255.0	18.0	292.0	266.0	140.0	304.0
DN32	38.0	1 ¼"	57.0	42.0	14.0	145.0	113.0	310.0	24.0	389.0	250.0	190.0	325.0
DN40	38.0	1 ½"	57.0	47.0	14.0	146.0	114.0	310.0	14.0	395.0	230.0	170.0	331.0
DN50	45.0	2"	66.0	59.0	16.0	186.0	133.0	330.0	26.0	425.0	293.0	216.0	343.0
DN15 855-Z	23.0	½"	23.0	21.0	7.0	48.0	64.0	259.0	13.0	284.0	285.0	138.0	165.0

Material specification

Nr	Component	Material
1	Body	Brass
2	Piston	Brass/ Nylon
3	Piston washer	NBR
4	Cotter pin	Brass
5	Lever	Brass
6	Backnut	Brass



Pressure & temperature ratings



Floats (for Pegler float operated valves)

Range	Code	Connection to lever arm*	Total (kg)
3" x 5/16" W	596022	5/16" W	0.03
4 1/2" x 5/16" W	596032	5/16" W	0.092
5" x 5/16" W	596033	5/16" W	0.114
6" x 3/8" W	596025	3/8" W	0.168
6" x 7/16" W	596026	7/16" W	0.170
8" x 3/8" W	596028	3/8" W	0.408
10" x 1/2" W	596029	1/2" W	0.803
10" x 9/16" W	596036	9/16" W	0.690
12" x 1/2" W	596038	1/2" W	0.788
12" x 5/8" W	596031	5/8" W	0.914

specification

- plastic or copper ball
- stud or claw attachment



Copper float sizes		
Range	Code	Total (kg)
4 1/2"	596001	0.121
5 1/2"	596003	0.183
6"	596004	0.219
8"	596006	0.442
10"	596008	0.686
12"	596009	1.005
14"	596010	2.420
15"	596011	2.390
16"	596012	2.766

Brass studs for copper floats. Required for copper float 4 1/2" to 12"

Connection to lever arm*	Code	Total (kg)
5/16" W	596039	0.020
3/8" W	596040	0.020
7/16" W	596041	0.055
1/2" W	596042	0.104
9/16" W	596043	0.098
5/8" W	596044	0.187



Claws for copper floats. Required for copper float 12" to 16"

Connection to lever arm*	Code	Total (kg)
9/16" W	596047	0.332
3/4" W	596048	0.313
7/8" W	596049	0.532



* W - Whitworth thread

Note: Studs generally required for float valves up to 2", Claws for 2 1/2" - 6" valves.

Note: Ball floats are only supplied in export shipments.

PB100 Ball valve




specification

- PN25 to ½" to 2"
- PN16 2 ½" to 4"
- full bore
- quarter turn operation
- red lever handle
- ½" to 4" sizes
- PTFE ball seals
- brass body
- PTFE gland
- taper thread BS EN 10226 (ISO7-1)
- ISO 228 BS 2771 parallel thread (PT)
- ANSI (NPT) American taper thread (AT)

DN	Connection	ISO7-1 Rc (taper)	ISO 288 G (PT)	ANSI (NPT) (AT)	Total (kg)	Cv (AT)	Kv (AT)
DN15	½"	270001	270021	270041	0.21	19.9	17.0
DN20	¾"	270002	270022	270042	0.27	48.0	41.0
DN25	1"	270003	270023	270043	0.43	81.9	70.0
DN32	1 ¼"	270004	270024	270044	0.63	141.6	121.0
DN40	1 ½"	270005	270025	270045	0.85	234.0	200.0
DN50	2"	270006	270026	270046	1.39	341.6	292.0
DN65	2 ½"	270007	270027	270047	3.16	626.0	535.0
DN80	3"	270008	270028	270048	4.26	994.5	850.0
DN100	4"	270009	270029	270049	6.03	1591.2	1360.0

*Cv - flow rate in US GPM at a pressure drop of 1 psi.

*Kv - flow rate in m3 per hour at a pressure drop of 1 bar.



Dimensions (mm)


	Do1	Do2	DN1/DN2	h1	L1	L2	M1	M2	slw1/sl2	U	V	Vh	Y	Z1	Z2
½"	24.0	28.0	DN15	18.0	25.0	27.0	8.0	100.0	24.0	17.0	29.0	69.0	26.0	13.0	15.0
¾"	30.0	35.0	DN20	18.0	28.0	32.0	8.0	100.0	30.0	17.0	32.0	76.0	26.0	16.0	18.0
1"	37.0	42.0	DN25	19.0	31.0	40.0	10.0	109.0	37.0	210	38.0	84.0	26.0	16.0	22.0
1 ¼"	46.0	53.0	DN32	19.0	35.0	46.0	11.0	133.0	46.0	23.0	45.0	97.0	27.0	18.0	27.0
1 ½"	53.0	61.0	DN40	20.0	43.0	46.0	12.0	133.0	53.0	23.0	78.0	110.0	30.0	26.0	28.0
2"	65.0	75.0	DN50	20.0	54.0	56.0	12.0	150.0	65.0	25.0	62.0	128.0	27.0	32.0	33.0
2 ½"	83.0	96.0	DN65	21.0	72.0	69.0	16.0	242.0	83.0	32.0	78.0	170.0	44.0	44.0	41.0
3"	97.0	112.0	DN80	22.0	73.0	87.0	16.0	242.0	97.0	32.0	85.0	188.0	46.0	46.0	49.0
4"	123.0	142.0	DN100	24.0	91.0	96.0	16.0	252.0	123.0	32.0	98.0	209.0	42.0	58.0	53.0

Material specification

Nr	Component	Material
1	Body	Brass
2	End piece	Brass
3	Ball, chrome plated	Brass
4	Stem	Brass
5	Seats	PTFE
6	Gland	PTFE
7	Gland nut	Brass
8	Lever handle, dip-coated	CP steel
9	Handle nut	Steel

Maximum pressure conditions

Size	Max Pressure (bar)	Min/Max Temperature (°C)	Test Pressure Shell (bar)	Test Pressure Seat (bar)	Max Pressure (psi)	Min/Max Temperature (°F)	Test Pressure Shell (psi)	Test Pressure Seat (psi)
½" to 2"	25.0	- 10°C + 120°C	37.5	27.5	362.6	14°F + 348°F	543.9	398.9
2 ½" to 4"	16.0	- 10°C + 120°C	24.0	17.6	232.1	14°F + 348°F	348.1	255.3




Pressure equipment directive category

Compressed air applications ½" - 1" SEP

1 ¼" - 4" CAT1

All other applications ½" - 4" SEP

Pressure & temperature ratings



JUNAID SANT. & ELECT. MAT. TR. LLC

P.O. Box 34862, Dubai, U.A.E.
Tel: +971 4 236 7723, Fax: +971 4 236 7750
E-mail: project@junaid.ae



7. Certificates



REPORT ON WATER POTABILITY OF BRASS AUTOMATIC AIR VENT (P775) & FORGED BRASS SPRING ACTION CHECK VALVES (1063) & FLOATVALVE PORTSMOUTH PATTERN HIGH PRESSURE (855 MOH)

Page 1 of 2

Client : Junaid San & Electrical Material Trading LLC
Address : Dubai, U.A.E.
Contractor : Not Provided
Consultant : Not Provided
Project : Quality Control Testing
Client Reference No : Not Provided
Sample Description : **Brass automatic air vent (P775) & Forged brass spring action check valves (1063) & Floatvalve Portsmouth pattern high pressure (855 MOH)**
Sample Identification : Not Provided
Source of sample : UK
Sample No. : Sample # 1, 4 and 8

Report No : **WR-1905/9255**
Lab Project No : **OG-786**
Lab Reference No : **WQ-1905/5128**
Date sample Received : 5/25/2019
Date test started : 5/25/2019
Date test completed : 6/9/2019
Report Date : 6/19/2019
Temperature of water used for extraction : **60°C**
Total number of extraction : After 7th Extraction
Tested by : MSH

Brass automatic air vent (P775) & Forged brass spring action check valves (1063) & Floatvalve Portsmouth pattern high pressure (855 MOH)



Test Data:

Description	BS 6920 - Part 1: 2000	Normal Tap Water (Before Test)	Results after 7th Extraction
Odour	No Discernible Odour	No Discernible Odour	No Discernible Odour
Flavour	No Discernible Flavour	No Discernible Flavour	No Discernible Flavour
Appearance	Clear	Clear	Clear

Parameter	BS 6920: Part 3 2000 Spec. Limits (Max.)	Normal Tap Water (Before Test)	Results
Aluminum Al µg/L	200	<20	<20
Iron Fe µg/L	200	<20	0,89
Manganese Mn µg/L	50	<5	1,40
Chromium Cr µg/L	50	<5	<5
Cadmium Cd µg/L	5	<0.5	0,82
Nickel Ni µg/L	50	<2	10,10
Lead Pb µg/L	50	<1	<1
Silver Ag µg/L	10	<1	<1
Arsenic As µg/L	50	<1	0,03
Mercury Hg µg/L	1	<0.1	<0.1
Selenium Se µg/L	10	<1	0,02
Antimony Sb µg/L	10	<0.5	<0.5
Barium Ba µg/L	1000	<100	24,16

Test Method : APHA 3120 B: 2005, BS 6920 Part 1:2000 section 2.6.
: The test specimen complies with BS 6920 Part 1:2000 section 2.6 specifications.
: The tested sample complies with the specification requirement of BS 6920: Part 2.2.1 & 2.4 in line with DWI (Drinking Water Inspectorate-UK) Regulation 31 (4), (b) Advice Sheet 8: Small Surface Area Section 2.0

Results relate only to the items tested.

This report shall not be reproduced except in full, without the written approval of the laboratory

Continued P/2



ماتيريال لاب - القوز - دبي، ص.ب: ١١٤٧١٧، هاتف: +٩٧١ ٤ ٣٤٠٥٦٧٧، فاكس: +٩٧١ ٤ ٣٣٩٥٦٢
ماتيريال لاب لخدمات الفحص ذ.م.م. - دي. آي. بي - دبي، ص.ب: ١١٤٧١٧، هاتف: +٩٧١ ٤ ٣٣٩٥٦٢
ماتيريال لاب لخدمات الفحص ذ.م.م.، أبو ظبي، ص.ب: ٦١٨٣١، هاتف: +٩٧١ ٢ ٥٥٠٣٠٤١، فاكس: +٩٧١ ٢ ٥٥٠٣٠٤١

Material Lab - Al Quoz - Dubai:- P.O. Box: 114717, Tel: +971 4 3405678, Fax: + 971 4 3405677

Material Lab Testing Services L.L.C. - DIP - Dubai:- P.O. Box: 114717, Tel: +971 4 3339562

Material Lab Testing Services L.L.C. - Abu Dhabi:- P.O. Box - 61831, Tel: +971 2 5503040 Fax: +971 2 5503041, Email: mlab@mlab.ae, Website: www.mlab.ae



REPORT ON WATER POTABILITY OF BRASS AUTOMATIC AIR VENT (P775) & FORGED BRASS SPRING ACTION CHECK VALVES (1063) & FLOATVALVE PORTSMOUTH PATTERN HIGH PRESSURE (855 MOH)

Page 2 of 2

Client : Junaid San & Electrical Material Trading LLC
Address : Dubai, U.A.E.
Contractor : Not Provided
Consultant : Not Provided
Project : Quality Control Testing
Client Reference No : Not Provided
Sample Description : **Brass automatic air vent (P775) & Forged brass spring action check valves (1063) & Floatvalve Portsmouth pattern high pressure (855 MOH)**
Sample Identification : Not Provided
Source of sample : UK
Sample No. : Sample # 1, 4 and 8

Report No : **WR-1905/9255**
Lab Project No : **OG-786**
Lab Reference No : **WQ-1905/5128**
Date sample Received : 5/25/2019
Date test started : 5/25/2019
Date test completed : 6/9/2019
Report Date : 6/19/2019
Temperature of water used for extraction : **60°C**
Total number of extraction : After 7th Extraction
Tested by : RTB

RESULT OF MICROBIOLOGICAL ANALYSIS#

Parameters	Test Methods	Units	Results	*Limits
Total Plate Count	APHA 9215B, 23 rd Ed. 2017	CFU/ml	390	500/ml
Total Coliforms	APHA 9222B, 23 rd Ed. 2017	CFU/100ml	Not Detected	Absent/100ml
Fecal Coliforms	APHA 9222B, 23 rd Ed. 2017	CFU/100ml	Not Detected	Absent/100ml
E.coli	APHA 9222B, 23 rd Ed. 2017	CFU/100ml	Not Detected	Absent/100ml
Pseudomonas aeruginosa	ISO 16266:2006E	CFU/100ml	Not Detected	Absent/100ml

Method Variation : None

#This test parameters were subcontracted to an accredited Lab.

Remarks :

The sample analyzed is of satisfactory quality with respect to above tested parameters.

*Limits: National primary drinking water regulation EPA 816-F-09-004, May 2009, US Environmental Protection Agency SOP No: RTL/MIC/SOP: 01, 02 & 12

Key Words: CFU - Colony Forming Units, ISO - International Organization for Standardization, APHA - American Public Health Association.



Syed N. Rizvi
Authorized Signatory
007 سيد نواز رضوي
Syed N. Rizvi
Manager (OGEC)

Results relate only to the items tested.

This report shall not be reproduced except in full, without the written approval of the laboratory.



ماتيريل لاب - القوز - دبي، ص.ب: ١١٤٧١٧، هاتف: ٣٤٠٥٦٧٨، فاكس: ٣٤٠٥٦٧٧
ماتيريل لاب لخدمات الفحص ذ.م.م. - دي. آي. بي - دبي، ص.ب: ١١٤٧١٧، هاتف: ٣٣٣٩٥٦٢
ماتيريل لاب لخدمات الفحص ذ.م.م. - أبو ظبي، ص.ب: ٦١٨٣١، هاتف: ٩٧١٢٥٥٠٣٠٤٠، فاكس: ٩٧١٢٥٥٠٣٠٤١

Material Lab - Al Quoz - Dubai:- P.O. Box: 114717, Tel: +971 4 3405678, Fax: + 971 4 3405677

Material Lab Testing Services L.L.C. - DIP - Dubai:- P.O. Box: 114717, Tel: +971 4 3339562

Material Lab Testing Services L.L.C. - Abu Dhabi:- P.O. Box - 61831, Tel: +971 2 5503040 Fax: +971 2 5503041, Email: mlab@mlab.ae, Website: www.mlab.ae



06 July 2020

To Whom It May Concern

Pegler Yorkshire hereby confirm that 855 Brass Float Valve & PB50 hose union Bib tap, are suitable for use with potable water applications.

If you have any other questions, please do not hesitate to ask.

Yours sincerely

A handwritten signature in blue ink, appearing to be "AM", written in a cursive style.

Abdelrahman Mostafa
Project Manager



CERTIFICATE OF CONFORMITY

PY Product: 855 Float valve

Description: Float valve MOH, Portsmouth pattern, high pressure

Number/Re:

Date: 11 Oct. 2024

Project:

Client: Junaid San & Elect Requ Trdg LLC

Dear Sir,

Pegler are proud to be involved with the above project and we hereby confirm that the following PY product on your order meets all of the relevant approvals, standards and have warranties in line with sound engineering practice.

Pegler is proud to confirm that the PY factory is BSI Kitemark Registered as per the following Certification. Further, we have been assessed and certified for the prestigious ISO 14001.2004.



For a full list of the exact specification & approvals, please refer to <http://www.pegleryorkshire.com/>

Pegler Products are manufactured in accordance with ISO 9001-2015 Quality Management Systems & are designed in line with the relevant British Standards where applicable. All products have been classified as Sound Engineering

Pressure & Temperature

Description	Minimum Operating Pressure (bar)	Maximum Cold Working Pressure (bar)	Maximum Hot Working Pressure (bar)
855 Float valve	No Minimum Operating Pressure	14.0 bar at temperatures up to 85oC	Not Suitable for Maximum Hot Working Pressure

Warranty

Valves and Fittings

Pegler Customcare 5 Year Guarantee - Terms and Conditions

Products are subject to a 5 year guarantee that is between Pegler and the final purchaser of the product.

The guarantee is subject to proof of purchase being supplied.

This guarantee does not affect any statutory rights the consumer may have in law.

The guarantee covers manufacturing or material defects and does not cover parts subject to normal wear and tear.

This product range has been designed for the use of homeowners, domestic and commercial applications and therefore the guarantee is subject to the product being properly selected for their intended service conditions.

The guarantee is not applicable where the product is fitted contrary to the conditions in the fitting instructions.

This is reinforced where valves are covered by the European Pressure Equipment Directive (PED97/23/EC) where Installation, Operating and Maintenance Instructions are supplied with each product and/or carton.

Provided it is installed correctly and receives adequate preventative maintenance it should give years of trouble –free service.

Abusive behaviour and accidental damage to the product are not covered by this guarantee.

The extent of this liability is limited to the cost of the replacement of the defective item and not to fitting or consequential damages.

Please do not hesitate to contact the undersigned should you require further clarification or information.

Aalberts integrated piping systems Ltd

St Catherine's Ave / Doncaster / S Yorkshire / DN4 8DF

01302 560 560 / uk.sales@aalberts-ips.com / www.pegler.co.uk

PEGLER MATERIAL SPECIFICATION.



Pegler Yorkshire

Pegler Yorkshire Test Certificate : 855

(in accordance with BS EN 12165/5 CW 617N)



Brass Raw Material is melted by induction furnace followed by compositional analysis using a Philips 1606 X-ray Fluorescence Spectrometer.

The material is then continuously cast into 150mm diameter billet followed by Direct extrusion, hot forging and machining.

Corrections are made to ensure that the material is in full compliance with British / European Standard BS EN 12164/5 CW617N

BRITISH STANDARD:

BS EN 12164 & 12165

MATERIAL No. (Symbol):

CW 617 N

(CuZn40Pb2)

COMMON NAME:

STANDARD 6040 BRASS.

COMPOSITION LIMITS.

<u>ELEMENT</u>		<u>Min %</u>	<u>Max %</u>
Copper	(Cu)	57.000	59.000
Tin	(Sn)	-	0.340
Lead	(Pb)	1.600	2.500
Iron	(Fe)	-	0.340
Nickel	(Ni)	-	0.340
Aluminium	(Al)	-	0.054
Total Of Other Impurities		-	0.240

All processes are operated under the control of our ISO 9001 Quality Management System.

Signed:

D. Ellis (Works Chemist)

Date:

10th March 2019

PEGLER YORKSHIRE GROUP LTD
ST. CATHERINES AVENUE, DONCASTER
SOUTH YORKSHIRE DN4 8DF ENGLAND
TELEPHONE 0044(0)1302 855656
FAX 0044(0)1302 761232



Pegler Yorkshire

Pegler Yorkshire Group Limited, St. Catherine's Avenue, Doncaster, South Yorkshire, DN4 8DF.

Telephone: +44 (0) 844 243 4400 Fax: +44 (0) 844 243 9870

Website: www.pegler-yorkshire.co.uk

CERTIFICATE OF CONFORMITY

This is to certify that the 855 & 856 Patterns of MOH Portsmouth Pattern Floatvalves supplied by Pegler Ltd are designed & manufactured in accordance with Pegler specifications and are controlled under the Quality Management System ISO 9001:2000.

PRODUCT TESTING

Products are sample tested hydrostatically to their relevant pressure ratings at the point of manufacture.

AGREED CONCESSIONS

Certified that the supplies detailed hereon have been inspected and tested in accordance with the conditions and requirements of the contract or purchase order and unless otherwise noted below conform in all respects to the specifications / drawing(s) relevant thereto.

S.M. Holloway
Quality Manager

CERTIFICATE OF CONFORMITY

This certificate confirms the declared products meet stated: performance capabilities, material standards and product standards where applicable and are rigorously subject to 3rd-party assessment by internationally renowned certification bodies.

Description

Product Series: PB100 Pegler Ball valve PB100

Size range: ½" – 2"

Pressure Rating: PN25

Material

Body Material: CW617N (BS EN 12165:2024, see below for standard defined limits)

Composition % (mass fraction)											
Grade	Element	Cu	Al	As	Fe	Mn	Ni	Pb	Sn	Zn	Other
CW617N	Min	57.0	-	-	-	-	-	1.6	-	Rem.	-
	Max	59.0	0.05	-	0.3	-	0.3	2.2	0.3	-	0.2

Certifications

- **ISO 9001** - products supplied by Aalberts Integrated Piping Systems are done so under a quality management system approved to BS EN ISO 9001: 2015 by an independent 3rd party certification body (Certificate Number FM 00305).

For Aalberts Integrated Piping Systems Ltd



Adam Lynaugh, Head of Quality UK



WRAS PRODUCT APPROVAL CERTIFICATE

Approval Number
241204729

Field of application	Products complying with the Water Supply (Water Fittings) Regulations 1999 (England & Wales), the Water Supply (Water Fittings) (Scotland) Byelaws 2014 and the Water Supply (Water Fittings) Regulations (Northern Ireland) 2009.
Approval holder	Aalberts Integrated Piping Systems Ltd.
WRAS directory section	2200
Product type	Valves
Model	PRV4 (5A2031) PRV4 (5A2032) PRV4 (5A2033) PRV4 (5A2034) PRV4 (5A2035) PRV4 (5A2036) PRESSURE REDUCING VALVES
Basis of compliance	Regulator Specifications (TCS) / BS Standard
Valid from	December 2024
Date of expiry	December 2029
Authorised by	 Ian Hughes, WRAS Approvals Manager



The certificate by itself is not evidence of a valid WRAS Approval.
The certificate must always be shared with the supporting letter.
Confirmation of the current status of an approval must be obtained from
the WRAS Approvals Directory (www.wrasapprovals.co.uk/directory/)



Certificate issued: 27th January 2025

JUNAID SANT. & ELECT. MAT. TR. LLC

P.O. Box 34862, Dubai, U.A.E.
Tel: +971 4 236 7723, Fax: +971 4 236 7750
E-mail: project@junaid.ae



8. Draft Warranty

Ref: JN/WC/2026/001

WARRANTY LETTER

Date: January 01, 2026

Project Name – IM_456_Hattan Villa
Landlord – Hattan Villa
Client – Hattan Villa
Plot No. – 3881109
Location – Al Thanyah Third
MEP Consultant – Al Manhal Engineering Consultants
Main Contractor – BW Interiors
MEP Contractor – BW Interiors MEP

This is to confirm that the following Pegler Brand items are manufactured in accordance with ISO 9001:2015 Quality Management Systems.

PEGLER - VALVES

- It carries warranty for 5 years from the date of TOC against manufacturing defects only.
- It does not extend to defects arising due to incorrect installation/application, misuse or normal wear and tear.
- Manufacturer's instructions manual must be strictly complied for warranty claim.
- TOC date cannot exceed beyond 6 months from date of invoice.

For,
M/s. Junaid Sanitary Electrical Material Trading LLC

Mr. Meraj Asad Khan
DIRECTOR OF SALES

JUNAID SANT. & ELECT. MAT. TR. LLC

P.O. Box 34862, Dubai, U.A.E.
Tel: +971 4 236 7723, Fax: +971 4 236 7750
E-mail: project@junaid.ae



9. Approvals

JUNAID SAN & ELE MAT TRDG. LLC

P.O. Box 34862, Dubai, U.A.E.

Tel: +971 4 236 7723, Fax: +971 4 236 7250

E-mail: project@junaid.ae

PREVIOUS PROJECT REFERENCE

PEGLER - VALVES

<u>PROJECT</u>	<u>MEP CONTRACTOR</u>	<u>CONSULTANT</u>	<u>PRODUCT</u>
AKOYA PARK – TOPANGA & RICHMOND 316 VILLAS	VOLT FLOW ELECTROMECHANICAL LLC	AECOM	PLUMBING VALVES & AIR VENT
TENORA HOTEL APARTMENT B+G+M+9 ON PLOT NO. RB-12 @ DUBAI WORLD CENTRAL DUBAI UAE	CONVERSION ELECTROMECHANICAL CO. LLC	SHANKLAND COX	FLOAT VALVES
ARABIAN RANCHES – 2/RASHA/ROSA/YASMIN COMMUNITIES – 382 VILLAS, DUBAI UAE	EFECO	AL GURG CONSULTANT	BIBTAP & FLOAT VALVES
ARABIAN RANCHES – 2/RASHA/ROSA/YASMIN COMMUNITIES - 382 VILLAS, DUBAI UAE	EFECO	LACASA (ARCHITECTS & ENGINEERING CONSULTANT)	FLOAT VALVES
PROPOSED AMITY UNIVERSITY ON PLOT NO. DIAC – D – 003 AT DIAC, DUBAI	TRINITY ENGINEERING	ARCH GROUP ENGINEERING CONSULTANT	ANGLE VALVES, FLOAT VALVES & BIB TAP
LG+G+4P+HC+SER+25 TYPE COMM & RES. AL SONDOS MANSION ON PLOT NO. 25021 AR DSO	TRINITY ENGINEERING	ARKITEKNIK INTERNATIONAL CONSULTING ENGINEERS	PLUMBING VALVES & STRAINER
PROPOSED G+M COMMERCIAL CENTRE	CORONA ELECTRO MECHANICAL WORKS LLC	ARIF & BINTOAK ENGINEERING CONSULTANT	GATE VALVE
AL FURJAN VILLAS – TERRACE HOMES – PACKAGES 4 DUBAI	CONVERSION ELECTROMECHANICAL	SHADEED ENGINEERING	BIB TAP

JUNAID SAN & ELE MAT TRDG. LLC

P.O. Box 34862, Dubai, U.A.E.

Tel: +971 4 236 7723, Fax: +971 4 236 7250

E-mail: project@junaid.ae

PREVIOUS PROJECT REFERENCE

PEGLER - VALVES

	CO.		
G+2P+23 STOREY RESIDENTIAL BUILDING FOR EMIRATES AT DSO, DUBAI	TRINITY ENGINEERING SERVICES LLC	ARCH GROUP	STOP VALVE & ANGLE VALVE
ADNOC SERVICE STATION AT MADINAT ZAYED GAYATHI	AL BADR CONTRACTING	ALTORATH ENGINEERING CONSULTANT	PLUMBING VALVES
PROPOSED G+M COMMERCIAL CENTRE	CORONA ELECTROMECHANICAL WORKS LLC	ARIF & BINTOAK ENGINEERING CONSULTANT	WATER HAMMER ARRESTOR
B+G+2 COMMERCIAL & RESIDENTIAL BUILDING	MODERN EXECUTIVE SYSTEM CONTRACTING	KHATIB & ALAMI	PLUMBING VALVES
AL FURJAN PROJECT (VILLAS & TERRACE HOME PACKAGE 6)	CONVERSION ELECTROMECHANICAL COMPANY LLC	SHADID ENGINEERING CONSULTANT	FLOAT VALVES
ABU DHABI RE- BEAUTIFICATION PACKAGE NO. 3 D&I ZONE NEW RETAIL AREA	ALKALINE ELECTROMECHANICAL	KHATIB & ALAMI	PLUMBING VALVES
G+2 PODIUM+13 STOREY+ROOF HOTEL TOWER ON PLOT NO. IBS 002, JABAL ALI 1 ST , 591 DUBAI	CONVERSION ELECTROMECHANICAL COMPANY LLC	ARCH GROUP CONSULTANT	ANGLE VALVE
VICEROY HOTEL RESORT,	CHINA STATE	P&T ARCHITECTS AND	ANGLE VALVE &

JUNAID SAN & ELE MAT TRDG. LLC

P.O. Box 34862, Dubai, U.A.E.

Tel: +971 4 236 7723, Fax: +971 4 236 7250

E-mail: project@junaid.ae

PREVIOUS PROJECT REFERENCE

PEGLER - VALVES

RESIDENCES, PALM JUMEIRAH, DUBAI	CONSTRUCTION ENGINEERING CORP.	ENGINEERING LTD/ECG	BIBTAP
2B+G+14+GYM RESIDENTIAL BUILDING ON PLOT NO. 373- 1246 AL BARSHA DUBAI	TECHNOMECH	ARCH GROUP CONSULTANTS	ISOLATING VALVES & ANGLE VALVE
G+1 VILLA ON PLOT NO. 376- 4706 @ AL BARSHA 2 ND DUBAI	POWER FACTOR ELECTROMECHANICAL WORKS LLC	ENG. ADNAN SAFFARINI	PLUMBING VALVES
DXB 12-27 AKOYA – GOLF RESIDENTIAL COMMUNITY	GHANTOOT GULF CONTRACTING	NAGA ARCHITECT DESIGNER PLANNER	PLUMBING VALVES
EMIRATES NATIONAL SCHOOL – RAK	GHANTOOT GROUP	HERBERGER ENGINEERING CONSULTING ENGINEERS	PLUMBING VALVES
B+G+1 VILLA ON PLOT NO. 363-323 @ AL MANARA – DUBAI	AL ARIF CONTRACTING CO. LLC	ENG. ADNAN SAFFARINI	PLUMBING VALVES
H.H SHEIKH SULTAN BIN TAHNOON BIN MOHAMMAD AL NAHYAN – PRIVATE VILLA @ NAD AL SHEBA	EFECO	SHANKLAND COX	WATER HAMMER ARRESTOR
DUBAI INN HOTELS – ZA'ABEEL	TRINITY ENGINEERING SERVICES	ARCHGROUP	ANGLE VALVE
H.H SHEIKH SULTAN BIN TAHNOON BIN MOHAMMAD AL NAHYAN – PRIVATE VILLA @ NAD AL SHEBA	EFECO	SHANKLAND COX	FLOAT VALVES & BIBTAP
PROPOSED 7 (G+4) RESIDENTIAL BUILDINGS – AL BARSHA SOUTH THIRD – DUBAI	POWER FACTOR ELECTROMECHANICAL WORKS LLC	GOLDEN SQUARE ENGINEERING CONSULTANT	PLUMBING VALVES

JUNAID SAN & ELE MAT TRDG. LLC

P.O. Box 34862, Dubai, U.A.E.

Tel: +971 4 236 7723, Fax: +971 4 236 7250

E-mail: project@junaid.ae

PREVIOUS PROJECT REFERENCE

PEGLER - VALVES

AKOYA OXYGEN 981 VILLAS	TRINITY ENGINEERING SERVICES LLC	KEO INTERNATIONAL	PLUMBING VALVES
AKOYA OXYGEN PHASE 1-547 VILLAS	TOWERS TECHNOLOGY CONTRACTING COMPANY LLC	KEO INTERNATIONAL	PLUMBING VALVES
WEST YAS – RESIDENTIAL VILLAS CONSTRUCTION – 1017 VILLA @ ABU DHABI	EFECO	JLA INTERNATIONAL ENGINEERING	FLOAT VALVE
G-007 AKOYA HOTEL APARTMENT	CONVERSION ELECTROMECHANICAL CO. LLC	CONIN INCORPORATED CONSULTANT	FLOAT VALVE AND ANGLE VALVE
PROPOSED G+5 STUDENT DUBAI ACADEMIC CITY	BRAYAN ELECTROMECHANICAL WORKS.	ARCHGROUP CONSULTANTS	PLUMBING VALVES
CONSTRUCTION OF 500 VILLAS @ OUD AL MUTEENA	EFECO	PARSONS OVERSEAS LIMITED	FOOT VALVE, FLOAT VALVE & BIBTAP
THE AKOYA OXYGEN 478 VILLAS PHASE 2 JANUSIA (VP6), H2 CLUSTER	BRAYAN ELECTROMECHANICAL WORKS	FRONTLINE INVESTMENT MANAGEMENT CO. LLC	PLUMBING VALVES
THE AKOYA OXYGEN 902 VILLAS PHASE 1 ZINNIA, ODORA & SYCAMORE CLUSTERS	COMMODORE CONTRACTING LLC	KEO INTERNATIONAL	PLUMBING VALVES
CONSTRUCTION AND MAINTENANCE OF 346 VILLAS	CONVERSION ELECTROMECHANICAL CO. LLC	JOUZY AND AXIANTA	PLUMBING VALVES

JUNAID SAN & ELE MAT TRDG. LLC

P.O. Box 34862, Dubai, U.A.E.


Tel: +971 4 236 7723, Fax: +971 4 236 7250

E-mail: project@junaid.ae

PREVIOUS PROJECT REFERENCE

PEGLER - VALVES

EMIRATES HOSPITAL, ON PLOT 2335660, AL QUSAIS 2ND, DUBAI, UAE	SAIFCO ELECTROMECHANICAL WORKS (LLC)	GREEN CONCEPT ENGINEERING CONSULTANTS	PLUMBING VALVES
MODIFICATION/FULL RENOVATION & FIT OUT WORK FOR THE NEW MUNICIPALITY COMMUNITY CENTER in AL YAHAR (AL AIN)	ARCO ELECTROMECHANICAL L.L.C	ARCAL ENGINEERING CONSULTANTS & INTERIOR DESIGN	PLUMBING VALVES
PROPOSED VILLA EXTENSION, PLOT NO. 3420542 AT JUMEIRAH SECOND	GAMMA CONTRACTING LLC	ARIF & BINTOAK CONSULTING ARCHITECTS & ENGINEERS	PLUMBING VALVES
2 VILLAS AT ZINNIA CLUSTER OF THE "AKOYA OXYGEN" MASTER DEVELOPMENT LOCATED ON PLOT NO. 9162809, AL YUFRAH 2, DUBAI, UNITED ARAB EMIRATES	GULF JEWEL MEP CONTRACTING L.L.C	BH.NS CONSULTANT ENGINEERING	PLUMBING VALVES
CIVIL & MEP WORKS AT EMARAT JEBEL ALI TERMINAL	AGNICE CONTRACTING LLC	FAN AL EBTIKAR ARCHITECTURAL ENGINEERING COMPANY	GATE VALVES & STRAINERS
THE CONSTRUCTION, COMPLETION AND MAINTENANCE OF (AL ZAHIA UPTOWN) COMPRISING OF PHASE A & B ON PLOT NUMBER: 483/186-6347 @ MUWALIH, SHARJAH-UAE	M/S. AL ARABIA ELECTROMECHANICAL	M/S. ENGINEERING CONSULTANTS GROUP (ECG), M/S. MIMAR EMIRATES ENG. CONSULTANT	PLUMBING VALVES
ADNOC GROUP SERVICES HUB	RCC	AL SUWEIDI	FLOAT VALVES

CONSULTANT		CLIENT		CONTRACTOR	
ICONIC آيكونيك للاستشارات المعمارية والهندسية ICONIC Architectural & Engineering Consultants Tel: +971 4 288 8819 Website: www.iconiconsultants.ae E-mail: info@iconiconsultants.ae		 حكومة دبي GOVERNMENT OF DUBAI  المكتب الهندسي ENGINEERING OFFICE		 ايجي بيلد للإشاعات ذ م م egy build construction L.L.C P.O Box: 251108 DUBAI-U.A.E TEL: 04-2976112, Fax: 04-2976114 MOB: 050-8100332 Email: egybuild@hotmail.com info@egybuild.ae web Site: www.egybuild.net	
PROJECT DETAILS		Commercial & Residential Building (G+P+6+R) On Plot No.4210102		LOCATION:	Al Warqa'a 1st, Dubai
MATERIAL SUBMITTAL REF NO.		(ICN-2023-11 MAT-288-158-R1)		DATE:	14-Dec-2024
MATERIAL SUBMITTAL					
DEPARTMENT		☐ STRUCTURAL ☐ ARCHITECTURAL ☐ ELECTRICAL ☐ MECHANICAL ☒ PLUMBING ☐ OTHER.			
MATERIAL DETAILS			LIST OF ENCLOSURES		
ITEM DESCRIPTION	MATERIAL SUBMITTAL FOR PLUMBING VALVES		☒	VENDER TECHNICAL LITERATURE	
SPECS REFERENCE			☒	COMPLIANCE STATEMENT	
BOQ REFERENCE			☐	COMPARISON SHEETS	
DRG. REFERENCE			☒	PREVIOUS TEST RESULTS	
MATERIAL SPECIFIED	PLUMBING VALVES		☒	COPY OF THE RELATED SPECS. & OTHER CONTRACT	
MATERIAL PROPOSED			☐	SAMPLE	
MANUFACTURER'S LOCAL SUPPLIER	JUNAID SANITARY & ELECTRICAL MATERIALS TRADING LLC		☒	LIST OF COMPLETED PROJECTS	
CONSULTANT'S PM/RE/PROJECT ENGINEER		NAME & SIGN		DATE:	
CONTRACTOR'S QA/QC		NAME & SIGN		DATE:	
CONTRACTOR'S PM/PE/ SITE ENGINEER		NAME & SIGN		DATE:	14-12-2024
For, ICONIC ARCHITECTURAL & ENGINEERING CONSULTANTS APPROVAL/ COMMENTS					
☐ APPROVED ☒ APPROVED AS NOTED ☐ REVISE & RESUBMIT ☐ REJECTED					
1.Reviewed and accepted as noted, Final approval subject to the Client approval.					
2.PEGLER made in UK is accepted as a make.					
3.Provide sample for final approval.					
4.Subject to mock up approval.					
5.Subject to final testing and commissioning approval.					
6. At the time material delivery at site contractor shall provide country of origin, Bill of lading and packing list along with material delivery at site.					
7.Material and Equipment delivery schedule shall in line with project program.					
8.Provide the Warranty certificate. Warranty shall be complied as per project contract from the date of TOC.					
9.PRV shall be submitted separately as per specification and calculation shall be submitted for final approval.					
CONSULTANT'S PM/RE/PROJECT ENGINEER		NAME & SIGN	zeeshan 	DATE:	26-12-2024
CONTRACTOR'S QA/QC		NAME & SIGN		DATE:	
CONTRACTOR'S PM/PE/ SITE ENGINEER		NAME & SIGN		DATE:	

City Beautification and Public
Projects Department

إدارة تجميل المدينة والمشاريع العامة

MATERIAL APPROVAL FORM (MAF)

Submission No :	164-SM-MEP-R1	Rev No. :	1
Date :	07-12-2024	☐ New Submittal	☒ Re-submittal
Project No :	PJ30059		
Project Name :	PJ-30059 - نادي و مصلى ذكر في الخوانيج		
End User :	Dubai Municipality	Supplier :	JUNAID SAN & ELE MAT TRDG LLC
Liaison Eng :	Ahmad Hasan Srur (Dubai Municipality)	MEP Eng. :	Ammar Rateb Ghafil Al Kubaisi (Dubai Municipality) / Ammar Rateb Ghafil Al Kubaisi (Dubai Municipality)
Consultant :	NAGA Architects	Contractor :	
Sub-contractor :		Trade :	
Description / Technical Letrate:			
FLOAT VALVE, ANGLE VALVE , BIPTAP, AIRVENT			
Attachments ☐ Sample ☒ Technical Data ☐ QA/QC Reports. ☐ Method Statement. ☐ Others			
Area of Application / Location			
Specs Ref.	Volume II Part B - Mechanical	Dwg. Ref.	P101,P200,M4-WS-100-M4-WS-104
BOQ ref.	TEMCH-Q1664_R4-05-2024		
Origin		Manufacturer Name:	PEGLER-UK
Local Agent		e-mail / Tel.	
Contractor's Attestation			
Material / Submittal Comply with Specifications ☐ Comply ☐ Non- Comply ☐ Alternative			
Details if Alternative:			
Certified By	CHC Building Contracting	Signature / Date	11-12-2024

For Consultant	
☐ No Objection	
☒ No Objection with Comments	
☐ Rejected	
Date forwarded to DM	11-12-2024
Date Received from DM	13-12-2024
Comments:	

For Dubai Municipality	
☐ Work may proceed.	
☒ Work may proceed subject to incorporation of comments.	
☐ Revise & re-submit, work may proceed subject to incorporation of comments.	
☐ Revise & re-submit, work may not proceed.	
☐ Rejected	
Comments:	
No Objection subject to incorporate all comments as detailed on pmweb system.	
DM Authorized:	Ahmad Hasan Srur
Signature / Date:	13-12-2024



City Beautification and Public Projects Department

إدارة تجميل المدينة والمشاريع العامة

MATERIAL APPROVAL FORM (MAF)

•Material sample shall be submitted for final approval. •Contractor to follow manufacture recommendation for installation / storage. •Method statement for installation / testing shall be submitted for review. •Warranty shall be from project taking over certificate date. •Material fabrication date shall be with 2 years from delivery date. •Subject to local authority regulation compliance. •certificate of origin and bill of lading shall be submitted along with material delivery. •Materials pressure rating shall withstand 1.5 system pressure.	
Consultant Authorized:	NAGA Architect 5
Signature / Date:	11-12-2024

Consultant Final Decision:	
☐ No Objection	
☐ No Objection with Comments	
☐ No objection with Cost saving	
☐ Rejected	
Date forwarded to Contractor	14-12-2024
Comments:	
•Material sample shall be submitted for final approval. •Contractor to follow manufacture recommendation for installation / storage. •Method statement for installation / testing shall be submitted for review. •Warranty shall be from project taking over certificate date. •Material fabrication date shall be with 2 years from delivery date. •Subject to local authority regulation compliance. •certificate of origin and bill of lading shall be submitted along with material delivery. •Materials pressure rating shall withstand 1.5 system pressure.	
Consultant Authorized:	NAGA Architect 5
Signature / Date:	14-12-2024
Note1: Cost Saving if any shall be submitted according to DM Procedures and Contract Conditions. Note2: Dubai municipality permission to proceed does not constitute acceptance or approval of materials developed or selected and does not absolve engineer/contractor and their subcontractors and suppliers from full compliance with contractual obligations including the quality of final product.	



MATERIAL APPROVAL FORM

REF: 18R1-1199-MS-MECH-Material
Submittal of Valves

PROJECT : 4 Twin Residential Buildings on Plot No. 170/A at Dibba Al Husn, Sharjah
for Department of Housing – Government of Sharjah

CLIENT : Department of Housing – Government of Sharjah

MAIN CONTRACTOR : M/s East Coast Contracting and Trading L.L.C.

NAME OF SUPPLIER /JUNAID SANITARY & ELECTRICAL MATERIALS TRADING) L.L.C

DESCRIPTION OF MATERIAL MATERIAL SUBMITTAL OF VALVES

MATERIAL BRAND / MANUFACTURER PEGLER

SPEC/BOQ/DWG. REF. Mechanical Specifications – Valves

(Enclose Copy)

SAMPLE SUBMITTED YES ☒ NO ☐ LITERATURE SUBMITTED YES ☒ NO ☐

FORM SUBMITTED BY MAIN CONTRACTOR

Gouda Mohamed 18-10-2024

Name Signature Date

FORM RECEIVED BY QHC

Wyndell Ancajas 18.10.2024

Name Signature Date

QHC COMMENTS

☐ Approved

☒ Approved with comments:
Refer to the attached comments sheet.

☐ Submittal is incomplete. The following is required

☐ Rejected, because

QHC REPRESENTATIVE APPROVAL

DATE 22/10/2024

QHC HEAD OFFICE APPROVAL

DATE 22/10/2024

CLIENT'S APPROVAL


DATE

FORM RECEIVED BY MAIN CONTRACTOR



Gouda Mohamed 22.10.2024



Name Signature Date



 فأبراج المستقبل FUTURE TOWERS	Material Submittal	
MR. AHMED ALHAJ ABDULLA MOHAMMED ALHABROOSH PROPOSED B+G+6+R RESIDENTIAL BUILDING ON PLOT NO. 673-0883 AT AL BARSHA SOUTH THIRD, DUBAI-UAE		
Consultant: Urban Habitat Architectural Consultants		Consultant Project # 22-063
Main Contractor: Future Towers Contracting		
Reference	TM-J125-MEP-MAT-PL-07	
Originator Company	M/s. Technomech Electromechanical Works	
Name of the Engineer In-Charge	Eng. Mohammad Shamsheer Alam	
Date	23/11/2024	To Be Returned
Material Type ☐ Architectural ☐ Structural ☐ Survey ☐ Electrical ☒ Plumbing ☐ HVAC ☐ Interior / Fitout ☐ IT / Home Automation ☐ Landscape ☐ Others		
Area :		
Material Detail		
Item Description	ANGLE VALVE	
Specs. / BOQ Ref.		
Drwg. Ref. & Location		
Material Specified	PEGLER	
Material Proposed	PEGLER	
Manufacturer / Supplier	JUNAID TRADING LLC	
Reason for Alternative		
Originator Signature :	Date: 23-11-2024	Time :
Main Contractor Signature :	Date: 23/11/24	Time :
Lead Consultant Received :	Date:	Time :
We certify that the Material submitted herewith has been reviewed and is in compliance with the contract drawings and specification except as otherwise stated		
FOR CONSULTANTS USE		
Consultant Comments : Comments / Signature / Date & time  ① Proposed make Pegler-UK is accepted. ② Values shall be delivered only from the approved suppliers. ③ Model 79 with red and blue indication for hot and cold water respectively. ④ Final approval after mock up approval. ⑤ Take ID/client approval for Angle Valves (Exposed) ☐ APPROVED ☒ APPROVED AS NOTED ☐ NOT APPROVED		
Employer's Signature :	Date:	Time :
Consultant Signature :	Date: 23/12/24	Time :
Main Contractor Received :	Date:	Time :
Sub Contractor Received :	Date:	Time :
CC :		
Corrections or comments made relative to submittals during this review do not relieve the contractor from compliance with the requirement and specifications. This check is for review of general conformance with the design concept of the project & general compliance with the information given in contract documents.		

Project:	LAYA Court Yard - [Residential + Retail] Building [B+G+5F+R] - Plot No. [6750295] @ Dubai Studio City - Dubai.				
[MS] Material Submittal					
Submittal No.:	MS-MEP-PL-007	Revision:	01	☐ New submittal ☒ Re-submittal	Date: 14-Dec-2024 Project Code: DXB-215
Material Description:	PLUMBING VALVES				
Origin:	UK	☐ Specified: PEGLER		☐ Alternative	
Discipline:	☐ Architecture ☒ Structure ☐ Electrical ☒ Mechanical ☐ Interior ☐ Other:				

Manufacturer		Local Supplier/Agent		Details	
Name:	PEGLER	JUNAID SANITARY & ELECTRICAL MATERIALS TRADING LLC			
Tel.:		04-2367723			
Fax.:		34862			
P.O.Box:		project@junaid.ae			
E-mail:					
Drawing Ref.:		Specs. Ref.:	Section 15110 - Valves	B.O.Q. Ref.:	
Attached:	☒ Data Sheet ☒ Sample ☐ Catalogue ☐ Profile ☐ Calculations ☒ Test Results ☐ Other				
QA/QC	Name:  Signature	Project Manager	Name: Engr. Ousama Alshawa	Signature: 	

Received By Consultant			
Name:	Signature	Date:	
Consultant Comments:			
↑ This Submittal only for (Gate, Angle, Globe, Check, Float & PRV) any other valves not included ↓ Locations & Sizes of Valves shall be as per Approved shop drawing ↓ warranty of 5 years as offered shall be from the Time of T.O.C. ↓ Pressure rate for Proposed Valves to be according to Project specifications. ↓ Float Valve body should be Bronze made. ↓ Coa & Bol Certificates and Packing list shall be Submitted along with each Material delivery ↓ all valves should be W RAS approved with Kitemark			
☒ Approved	☒ Approved With Comments	☒ More Information Required	☒ Rejected
Consultant	Name	Signature	Date
Commented By		hassan eldn	20/12/2024
QA/QC			
Resident Engineer	Nazar Bairouti		20/12/2024
Received Back By Contractor			20/12/2024

* No objection for using Pegler UK

Last Update: 01-Jan-2024

Client:

M/s. W Twenty Three Investments LLC

The Consultant:

BEL-YOAHAH
ARCHITECTURAL & ENG. CONSULTANTS



The Main Contractor:



AL KITBI CONTRACTING L.L.C.
P.O.BOX 48014 Ph : 04 3595593, FAX : 04 3595591
e-mail : alkitbi.com@gmail.com

Project: B+G+R Floor Commercial Building on Plot no. 3620452 at Umm Suqeim Second, Dubai.

MATERIAL SUBMITTAL

Ref. No.

MS-MEP-PL-01

Rev. No.

1

Material Detail

Item Description	Gate Valve and Angle Valve- Pegler-UK	List of Enclosure (Tick the Related Box) ☒ Vendor's Technical Literature ☐ Compliance Statement ☒ Previous Test Results ☐ Copy of the Related Specs. ☐ Sample ☒ List of Previous Projects Done ☐ Others (Specify): ☒ INDUSTRIAL LICENCE
Specs. / BOQ / Drwg. Reference	-	
Material Specified		
MEP-Subcontractor	Sharifa Electromechanical works LLC	
Manufacturer / Local Supplier	Junaid san & ele mat trdg LLC	
Reason for Alternative		
Remarks		

Main Contractor Statement: We certify that the material submitted herewith has been reviewed in details and in compliance with the contract drawings and specifications except as otherwise stated here above.

Main Contractor Signature:

Date:

5-Dec-24

Bel-Yoahah Received:

Date:

Bel-Yoahah Resident Engineer's Comments:

The proposed 10751 Bronze Gate Valve is accepted as mentioned in the compliance statement.
 The proposed ART 79 Pegler – UK Angle Valve is accepted.
 Sample shall be submitted for review and final approval.

09/12/2024

☐ APP - Approved

☒ AAN - Approved As Noted

☐ NA - Not Approved, Resubmit

☐ IR - Incomplete, Resubmit

Bel-Yoahah RE Signature:

Amit

Date:

09/12/2024

Main Contractor Received:

Date:

1:58 PM

Corrections or comments made relative to submittals during this review do not relieve the contractor from compliance with the contract requirement and specifications. This check is only for review of general conformance with the design concept of the project.

Employer	Consultant	Contractor
Project	 ALIGN ENGINEERING CONSULTANTS AND INTERIOR DESIGN LLC	AL KITBI CONTRACTING L.L.C
PROPOSED G+1 RESIDENTIAL VILLA PLOT NO 3323106 JUMIERA FIRST DUBAI-UAE		DATE : 18/11/2024
		Ref. No AKC-MS-MEP-PL-04 Rev 01

MATERIAL SUBMITTAL

WE ARE FORWARDING HEREWITH ☐ UNDER SEPARATE COVER ☐ THE MATERIAL LISTED BELOW:-

THIS SUBMITTAL IS INTENDED FOR (TICK AS APPROPRIATE)

TRADES ☐ Architectural ☐ Civil ☒ Mechanical ☐ Electrical ☐ Others

TYPE: ☐ SAMPLE

DESCRIPTION OF MATERIAL : Gate Valve (Pegler - UK) & Angle Valve (Grohe)

SPECIFICATION OR CONTRACT DOCUMENT REFERENCE :

MANUFACTURER (Name, Address & Country of Origin) :

SUPPLIER AND/OR LOCAL AGENT (CONTACT NUMBER) : JUNAID SANT. & ELECT. MAT. TR. LLC P.O. Box 34862, Dubai, U.A.E.
Tel: +971 4 236 7723

AREA/LOCATION OF USE :

DESCRIPTION OF SAMPLE :

SPECIFICATION COMPARISON SHEET :


COMPARISON IN CASE OF ALTERNATE SUBMITTAL :

TECHNICAL DETAIL :

DRAWING NO. : / Title:

THE CONTRACTOR:

We certify that this submitted material are strictly complying with the Contract Documents except for the deviations specified in the attachments otherwise stated

ISSUED BY CONTRACTOR	RECEIVED BY:	RECEIVED BY:
SIGNATURE: 	SIGNATURE:	SIGNATURE:
STAMP: 	STAMP	STAMP
NAME: Azmeel Ahmed	DATE:	DATE:
DATE: 18/11/2024		

TO: CONTRACTOR

YOUR SUBMITTAL HAVE BEEN REVIEWED AND GIVEN THE APPROVAL CATEGORY AS NOTED BELOW:
FOR DETAILS OF OUR COMMENTS, REFER TO THE ATTACHED CONSULTANT COMMENTS:

☐ TICK IF ATTACHED

CONSULTANT'S Remarks

- Approved with comments:
- 1-No objection for proposed brands Grohe for Angle Valves and Pegler-UK for Gate valves
 - 2-Sample boards with different options of valves to be provided for our approval and owner approval prior to procurement of the material.
 - 3-Samples of angle valves must match with ID finishes

A
B
C
D

SUBMITTALS

☐ Approved ☐ Not Approved, Resubmit

☒ Approved as Noted ☐ Incomplete, Resubmit

Date: _____ Signature: _____

Correction or comments made relative to submittals during this review does not relieve the Contractor from compliance with the requirements of the drawings and specifications. This check is only for review of general conformance with the design concept of the project and general conformance with the design concept of the project and general compliance with the information given in the contract documents. The Contractor is responsible for confirming and correlating all dimensions, selecting fabrication process and techniques of construction, coordinating his work with that of other trades, and performing his work in a safe and satisfactory manner.

CONSULTANT	RECEIVED BACK BY:	RECEIVED BACK BY: Contractor
SIGNATURE: WR	SIGNATURE:	SIGNATURE
STAMP: 23-11-2024	STAMP:	STAMP:
DATE:	DATE:	DATE:

APPROVAL STATUS CODE: ☒ APPROVED ☐ APPROVED AS NOTED ☐ REVISE & RESUBMIT ☐ REJECTED

Falcon Island Villa Development (North and South), Al Hamra Village Al Jazeera Al Hamra, RAK, UAE

Client:  Al Hamra Real Estate Development	Contractor:  Construction & Reconstruction Engineering Company (CRC)	Sub-Consultant:  International Engineering Consultant	Lead Consultant:  JT & Partners Architectural and Engineering Consultant	MEP Contractor:  E7M Electromechanical Works Contracting L.L.C
--	---	--	--	---

MATERIAL / EQUIPMENT APPROVAL SUBMITTAL

Ref: CRC-FIV-E7M-MS-PL-36

Rev: 00

Submission Date: 06-11-2024

Discipline:	1. Civil ☐	3. Mechanical ☒	5. Plumbing ☐	7. Interior Design ☐	9. Authorities ☐
	2. Architectural ☐	4. Electrical ☐	6. Firefighting ☐	8. Landscape ☐	10. Speciality/Miscellaneous ☐

Title: MATERIAL SUBMITTAL FOR VALVES AND ACCESSORIES

Material Description: VALVES AND ACCESSORIES

Drawing Ref. N/A

Specification Ref. (add Main Criteria if necessary) Section: 221100 – VALVES

Shipment ☐ Land ☒ Sea ☐ AirAnticipated date to be on site
Early 01-11-2024 Late 20-11-2024Manufacturer
☐ Local ☒ Imported
Name: M/s. ALBERTS INTEGRATED PIPING SYSTEMS – UK (PEGLER)
Address: SOUTH YORKSHIRE, ENGLAND UK.Supplier
☐ Local ☒ Imported
Name: M/s. JUNAID SAN & ELE MAT TRDG LLC
Address: P.O.BOX: 34862. Dubai, U.A.E

Sub-Contractor

We confirm that the material hereby submitted is suitable for the conditions of use and confirms with the contract specification and all applicable codes, standards and statutory requirements. Acceptance of this material submittal does not alter in anyway whatsoever our contractual or common obligations and responsibilities. Where the submittal is in any way in variance with the specification, such variations must be identified and brought to the attention of the engineer or engineer's representative on this form

ENCLOSURES

- ☐ Relate Drawings
- ☒ Other contract documents
- ☒ Compliance statement
- ☒ Commercial/ Trade licence
- ☒ ISO-Certificate (If applicable)
- ☒ Catalogue/ Data sheets
- ☒ Test certificates/ MTC
- ☒ Sample submitted
- ☒ Warranty letter (Draft)
- ☒ Previous Approval (s)
- ☒ List of previous projects executed
- ☒ Photographs
- ☐ Alternate selection comparison list
- ☐ Method statement

Issued by the MEP Contractor:

Received by the Main Contractor:

Received by the Consultant:

Signature/Stamp

Signature/Stamp

Signature/Stamp

Project Manager: Sajjad Akram
 Technical Manager: Hamid Masoodi
 Project Engineer:

Technical manager: Remon Kamel
 Project Manager: Mohamed El Sayed
 MEP Coordinator:

Date: 06-11-2024

Date: 06-11-2024

07 NOV 2024

Falcon Island
Project # JTP-21006A
RAK - UAE

THE ENGINEER'S REVIEW/ COMMENTS:

No objection For Gate Valves, Bib TAPE and Mechanical Float Valve manufactured From PEGLER made in England UK, Subject to the following:

- ① To provide sample for final approval & installation acceptance at the site.
- ② Quantity & size shall be as the project specifications.
- ③ A manufacturer warranty (5 years) shall be provided, commencing from the TOC.
- ④ The contractor is responsible for ensuring that the supplier is capable of meeting the project program

STATUS	Code A ☐	Code B ☒	Code C ☐	Code D ☐	Code E ☐
	Approved	Approved as Noted	Revise & Resubmit	Rejected	Acknowledge/Noted as Received

Issued by the Engineer:

Received by the Contractor:

Signature/Stamp

Signature/Stamp

Date:

Date:

15 NOV 2024

16 NOV 2024

RECEIVED

Correction or comments made relative to submittals during this review DO NOT relieve the contractor from compliance with the requirements of drawings and specifications. This check is only for review of general conformance with the design concept of the project.